



DAV PUBLIC SCHOOL

SECTOR-6, CDA, CUTTACK-753014

(Affiliated to C.B.S.E., New Delhi, Affiliation No.-1530046, School No.-15341)

Ref.No : DAV(CDA)/787/2024

Date.....20.04.2024

QUOTATION CALL NOTICE

Sealed quotations are invited by the undersigned from reputed Agency/contractor for the supplying and laying of Paver Block at DAV Public School, CDA – 6, Cuttack. Interested Agencies/Contractors may submit their quotations for the above said purpose in the prescribed format in their letter head with seal & signature on or before date: 30.04.2024 along with the specifications by 4:00 pm at **DAV Public School, CDA-6, Cuttack-14**. The quotations received either after the stipulated date & time due to postal delay or incomplete in any respect shall not be considered. The quotations without **GST Certificate & PAN** shall not be considered. The envelope containing the quotation must be written as “**QUOTATION FOR PROVIDING AND LAYING PAVER BLOCK**”. The quotations should be strictly as per the Type & Description mentioned on the Quotation Form. The undersigned reserves the right to cancel any / all the quotations without assigning any reasons thereof.

TERMS & CONDITION

1. Rates are to be quoted for supplying and laying of material which included transportation, loading, unloading, all taxes applicable.
2. The school authority does not bind to accept the lowest quotation & reserves the right to accept or reject any quotation without assigning any reasons whatsoever.
3. Payment will be made after completion of work and submission of bill.
4. The materials approved by the competent authority only shall be used.
5. The bidders are requested to visit the work site before quoting the price.

Copy to:-

1. The Notice Board of the School for information of the public / persons concerned on this profession.
2. The Principal, DAV Public School: Cspur/ Pokhariput/ Kalinga Nagar /Unit-VIII/ LRDAV/ Rajabagicha with a request to kindly take necessary steps to display the notice on the school notice board & website for information of the public/person concerned.
3. The concerned file for record.

[Handwritten Signature]
20/04/24
PRINCIPAL
PRINCIPAL
DAV Public School
Sector-6, CDA, Cuttack-14
School No.15341
Affiliation No. 1530046

[Handwritten Signature]
PRINCIPAL
PRINCIPAL
DAV Public School
Sector-6, CDA, Cuttack-14
School No.15341
Affiliation No. 1530046

MANAGED BY - DAV COLLEGE MANAGING COMMITTEE, CHITRA GUPTA ROAD, NEW DELHI

Address - Sector-6, CDA, Cuttack-753014 (Odisha) Phone No.- 0671-2503443, 2505909

Email : davcda2018@gmail.com / davcda2004@yahoo.com Website : www.davcda.org

DAV PUBLIC SCHOOL, CDA-6, CUTTACK

QUOTATION FOR PROVIDING AND LAYING PAVER BLOCK

Name of the Agencies/Contractors _____

Address _____

Contact No. _____

GST No. _____

PAN No. _____

Sl. No	Particulars	Unit	Rate/Unit
A. Labor Component			
1	Demolishing cement concrete manually/mechanical means including disposal of material all complete	CUM	
2	Taking out existing CC interlocking paver blocks including removal of rubbish etc., disposal of unserviceable material to the dumping ground all complete	SQM	
3	Earth work by mechanical / manual in rough excavation, rolling each layer with 1/2 tons roller or wooden or steel rammers, and rolling every 3rd and top-most layer with power roller of minimum 8 tones and dressing up for roads or filling up ground depressions all complete	CUM	
4	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, lift up to 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed all complete	CUM	
5	Surface dressing of the ground including removing vegetation and inequalities not exceeding 15 cm deep and disposal of rubbish all complete	CUM	
6	Providing, Laying, spreading and compacting graded stone aggregate (size range 53 mm to 0.075 mm) to wet mix macadam (WMM) specification including premixing the material with water at OMC in for all leads & lifts, laying in uniform layers in sub- base / base course on well prepared surface and compacting with vibratory roller all complete	CUM	
7	Providing and Laying 60mm thick factory made cement concrete interlocking paver block of M -40 grade made by block making machine with strong vibratory compaction, of approved size, design &	SQM	

	shape, laid in required color and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with fine sand etc. all complete as per the direction of Engineer-in-charge.		
8	Providing and Laying in position cement concrete of specified grade : 1:3:6 (1 Cement : 3 coarse sand derived from natural sources : 6 graded stone aggregate 20 mm nominal size derived from natural sources) all complete.	CUM	
9	Brick work with common burnt clay modular bricks in Cement Mortar 1:6 (1 cement: 6 coarse sand).	CUM	
10	12 mm cement plaster of mix :1:6 (1 cement: 6 fine sand) all complete	SQM	
11	Neat cement punning all complete	SQM	
12	Fixing factory made precast RCC perforated drain covers, having concrete of strength not less than M-25, reinforced with 8 mm dia four nos longitudinal & 9 nos cross sectional T.M.T. hoop bars, including providing 50 mm dia perforations @ 100 to 125 mm c/c, including providing edge binding with M.S. flats of size 50 mm x 1.6 mm complete, all as per direction of Engineer-in-charge.	EACH	

B. Material Specification

1	Ordinary Portland Cement 43 grade	ACC, Ambuja, Ultratech, JK or Equivalent
2	Paver Block	60 mm thick M40 grade, strength test result certificate have to submit from Govt. registered Lab

Note: 1. Rates should be inclusive of GST.

2. Please provide seal & signature on all pages.

3. Detailed Information about the location, Phone No., E-mail address and Fax No. of the Agency/Contractor should be attached along with the quotation.

Signature of agency/contractor with seal

Date: